

15135-70139-0000

Form CP-3  
Rev. 6-26-62

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
APR 17 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Tilco et al

Complete Address: 815 Wichita Plaza Wichita, Ks.

Lease Name Herrick Well No. 1

Location C SW NE Sec. 18 Twp. 17 Rge. 23 (E) (W) X

County Ness Total Depth 4539

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Leben Drlg.

Address: Wichita, Kansas License No. \_\_\_\_\_

Operation Completed: Hour 2:15 P Day 14 Month 4 Year 1968

The Above well was plugged as follows:

RTD 4539' 8 5/8 csg set at 320' cwc 185 sc. Cem. Mat. 50-50 Poz cem. W/6% gel.

Gunned pipe, circulated heavy mud, set cementing plug and displaced 70 sc cement thru

drill pipe. Heavy mud to 300' set cementing plug and displaced 20 sc cement thru drill

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base

of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 4/17/68

INV. NO. 7595-W

Signed: [Signature]  
Well Plugging Supervisor