

15-135-20527-000

Form CP-3
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
DEC 23 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Alpine Drilling Company, Inc.

Complete Address 800 Bitting Bldg., Wichita, Kansas 67202

Lease Name Anspaugh Well No. 1

Location C NE SE Sec. 19 Twp. 17 Rge. (E) (W) 23

County Ness Total Depth 4468'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Gabbert & Jones Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 2:30 P Day 20 Month 12 Year 1971

The above well was plugged as follows:

RTD 4468' 8 5/8 csg set at 293' cwc Cmt. Mat. 50-50 poz W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 700' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 270' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Geo F. Warrup
Well Plugging Supervisor

INVOICED

DATE 1-7-72

INV. NO. 4859-W