

15-135-30223-00-00

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

SEP 28 1966
09-23-1964
CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Donald C. Slawson

Complete Address: 408 One Twenty Building, Wichita, Kansas

Lease Name Goatley... "B" Well No. 1

Location C SE NW Sec. 7 Twp. 19 Rge. 21 (E) (W) X

County Ness Total Depth 4406'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Co, Tools

Address: License No.

Operation Completed: Hour 4:30 P Day 19 Month 9 Year 1966

The Above well was plugged as follows:

RTD 4406' 8 5/8 csg set at 324' cwc 225 sc,
Gunned pits, circulated heavy mud, set cementing plug at 540' and displaced
30 sc cement thru drill pipe. Heavy mud to 320' set cementing plug and displaced
20 sc cement thru drill pipe. Heavy mud to 40' set cementing plug 1/3 sc hulls
and 10 sc cement to base of celler. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 9/26/66
INV. NO. 3979-u