

15-135-30065-00-00

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
07-15-1974
JUL 15 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Palomino Petroleum

Complete Address 304 Insurance Bldg., Wichita, Kansas 67202

Lease Name DeWald "C" Well No. 1

Location C NE SW Sec. 7 Twp. 19 Rge. (E) (W) 21

County Ness Total Depth 4404'

Abandoned Oil Well XX Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor Pipe Pullers, Inc.

Address Box 486 Ellinwood, Kansas 67526 License No. 462

Operation Completed: Hour 10 A Day 12 Month 7 Year 1974

The above well was plugged as follows:

Total Depth 4404' 8 5/8 csg set at 312' cwc 200 sk.

4 1/2 csg set at 4403' ow 125 sk cmt.

4 1/2 csg perf. 4286'.

Set 4 1/2 wood plug at 4200' -poured 20' sand -dumped 3 sk cmt W/dump bailer. (4150-4200)

4 1/2 csg 2-stage collar at 1200' -circ. to surface with 600 sk cmt.

No pipe recovered.

Filled 4 1/2 csg with mud to 515' -set rock & sand bridge (515-500)

Filled with readymix cement from 500' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo T. Massey
Well Plugging Supervisor

INVOICED

DATE 7/16/74

INV. NO. 9525-W