

15-135-20365-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
SEP 8 1970
CONSERVATION DIVISION
Wichita, Kansas

09-08-1970

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Nadel & Gussman

Complete Address 1714 First National Building, Tulsa, Oklahoma

Lease Name Boese Well No. 1

Location C NE SE Sec 14 Twp. 19 Rge. (E) (W) 21

County Ness Total Depth 4373

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Sage Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 10:30 P Day 3 Month 9 Year 1970

The above well was plugged as follows:

RTD 4373' 8 5/8 csg set at 330' cwc

Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 40 sk
cmt thru drill pipe. Heavy mud to 310' set cementing plug and displaced 25 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: K. F. Massey
Well Plugging SupervisorDATE 9/8/70INV. NO. 2491-44