

15-135-20471-00-00

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
SEP 14 1971
CONSERVATION DIVISION
Wichita, Kansas

09-14-1971

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Leben Drilling, Inc.
Complete Address 200 W. Douglas Wichita, Kansas
Lease Name Antenen Well No. 1
Location C E/2 NW SE Sec. 23 Twp. 19 Rge. (E) (W) 21
County Ness Total Depth 4480'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Co. Tools
Address License No.
Operation Completed: Hour 9 P Day 9 Month 9 Year 1971

The above well was plugged as follows:

RTD 4480' 8 5/8 csg set at 370' cwc Cmt. Mat. 50-50 poz W/4% added gel.
Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 360' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 9-14-71
INV. NO. 4316-w