

15-135-20317-00-00

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT RECEIVED
STATE CORPORATION COMMISSIONJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202FEB 5 1970
CONSERVATION DIVISION
Wichita, Kansas

02-05-1970

Operator's Full Name Adair Oil and J. E. Morris

Complete Address Box 7011 Wichita, Kansas

Lease Name Atenen Well No. 1

Location C NW NE Sec. 25 Twp. 19 Rge. (E) (W) 21

County Ness Total Depth 4445

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Rains & Williamson

Address Wichita, Kansas License No.

Operation Completed: Hour 10:30A Day 1 Month 2 Year 1970

The above well was plugged as follows:

RTD 4445' 8 5/8 csg set at 250' cwc. 175 sk. Cmt. Mat. 50-50 poz 6% gel.

Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 16 sk cmt
to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INDEXED
DATE 2/6/70
INV. NO. 1376-WSigned: Leo F. Murray
Well Plugging Supervisor