

15-135-20545-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 6720202-08-1972
RECEIVED
STATE CORPORATION COMMISSION
FEB 8 1972
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Acme Oil Corporation

Complete Address 6235 W. Kellogg Wichita, Kansas

Lease Name Meyer Well No. 1

Location C SE SE Sec. 21 Twp. 19 Rge. (E) (W) 21

County Ness Total Depth 3880'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor B & B Drilling. (Rotary)

Address Wichita, Kansas License No.

Operation Completed: Hour 9 A Day 6 Month 2 Year 1972

The above well was plugged as follows:

RTD 3880' 8 5/8 csg set at 511' cwc Cmt. Mat. 50-50 poz cmt W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 50 sk

cmt thru drill pipe. Heavy mud to 420' set cementing plug at 420' displaced 25 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 2/11/72
INV. NO. 5151-WSigned: Paul A. Mursey
Well Plugging Supervisor