

15-135-00333-0000

Form CP-3  
Rev. 6-26-62

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

JAN 15 1964

01-015-1964  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Walters Drg Co & Ferguson Oil Co

Complete Address: 510 Orpheum Bldg Wichita, Kansas

Lease Name Meyer Well No. C-1

Location GSW SW Sec. 21 Twp. 19 Rge. (E) (W) 21

County Ness Total Depth 4399

Abandoned Oil Well Gas Well Input Well SWD Well D & A x

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractors: Glenn & Smith

Address: Ellinwood, Kansas License No. 396

Operation Completed: Hour 10AM Day 8 Month 1 Year 64

The Above well was plugged as follows:

8 5/8" 490' circulated with cement - 5 1/2" 4396' with 150 sax cement.

Sanded back to 4380', set 4 sax cement with dump bailer - pulled 3300'  
5 1/2" - filled hole with fresh pit mud 490', set 20 sax cement at 490',  
heavy pit mud to 200', set 20 sax cement at 200', heavy pit mud to 35'  
bridged and filled to bottom cellar with cement ( 10 sax )

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

DATE 1/15/64  
INV. NO. 8464-W