

15-135-20479-00-00

Form CP-3
Rev. 6-4-68

KANSAS

AL
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

SEP 28 1971

CONSERVATION DIVISION
Wichita, Kansas

09-28-1971

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Chief Drilling & Leber Oil

Complete Address 905 Century Plaza Wichita, Kansas 67202

Lease Name Moore Well No. 1

Location SE SW NW Sec. 34 Twp. 19 Rge. (E) (W) 21

County Ness Total Depth 4450'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Leber Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 19 P Day 19 Month 9 Year 1971

The above well was plugged as follows:

RTD 4450' 8 5/8 csg set at 356' cwc Cmt. Mat. 50-50 per W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 390' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Marney
Well Plugging Supervisor

DATE 9-29-71
INV. NO. 4396-4