

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-135-30009-00-00
15-65-

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name PICKRELL DRILLING COMPANY

Complete Address 110 N. MARKET, SUITE 205, WICHITA, KS 67202

Lease Name FOOS Well No. 1

Location C. NE. SW Sec. 31 Twp. 19 Rge. 21 (East)(West)

County NESS Total Depth 4409'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor KELSO CASING PULLING

Address Box 176, CHASE, KS 67524 License No. _____

Operation Completed: Hour: 12:00 Noon Day: 23 Month: 8 Year: 1982

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

The 8 5/8" S.P. was set @ 402' w/200 sq. Cement. 5 1/2" casing set @ 4402' w/100 sq. Cement. 5 sq. sand and 5 sq. cement set in the 5 1/2" at 4350'. Recovered 2500' of 5 1/2".

On 8-18-82, we pumped 3 sq. hulls and 19 sq. gel, then leaks developed around the surface pipe under pumping pressure of 300 lbs. Another sack of hulls was added, knotted gummy sacks and pushed down hole w/11 sq. gel. Casing continued to leak and operation (over)

Amount of Surface Casing: 402'

I hereby certify that the above plugging instructions were given as herein stated.

Signed: R. B. Arlinton
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Signed: _____
Conservation Division Agent

INVOICED
DATE 9-9-82
INV. NO. 1081-W

Rec. 9-2-82

was discontinued until 8-23-82. At that time, 930' of 2 1/2" pipe was run in the hole and 70 sq. ft. of 50-50 Poz-mix w/4% gel-3% C.C. was pumped, followed by 2 hulls, 10 sq. ft. gel and then 100 sq. ft. Cement to finish. Due to the leaking in, surface pipe, cement top will be wire lined, and if top is not at the surface, additional cement will be added.