

15-135-20019-00-00

Form CP-3  
Rev. 6-26-62

KANSAS

**STATE CORPORATION COMMISSION**

**CONSERVATION DIVISION AGENT'S REPORT**

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

RECEIVED  
MAY 9 1967  
05-09-1967  
STATE CORPORATION COMMISSION  
WICHITA, KANSAS

Operator's Full Name Cities Service Oil Company

Complete Address: Box 308 Great Bend, Kansas 67530

Lease Name Moore "B" Well No. 7

Location App. C SE NE Sec. 30 Twp. 19 Rge. 21 (E) (W) X

County Ness Total Depth 4460'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Knights Casing Pulling Co.

Address: Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 12:30 P Day 8 Month 5 Year 1967

The Above well was plugged as follows:

Total Depth 4460' 8 5/8 csg set at 506' cwc 275 sc.

4 1/2 csg set at 4459' cw 150'

PB 4444' Top perf. 4412' Filled with sand to 4400' and dumped 4 sc cem. with dump bailer.

Recov. 2614' of 4 1/2 csg.

Set plug and 20' rock bridge at 500'

Filled to surface with 6 yds readymix cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 5/11/67

INV. NO. 5195-U

Signed: Red Massey  
Well Plugging Supervisor