

State of Kansas



15-101-200&0-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
APR 1 - 1974
4-1-74
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Bigheart of Abercrombie Drlg. has this

date requested permission to plug the following described well:

Mr. Bigheart guarantees payment of the plugging fee.

Operator's full Name: Abercrombie Drlg., Inc.

Complete Address: 801 Union Center, Wichita, Kansas

Lease Name: Ware Well No. 3

Location: NW NW Sec. 24 Twp. 19 Rge. (E)(W) 28

County: Lane Total Depth 4392' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Bigheart was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 750' and displace
70 sk cmt thru drill pipe. Heavy mud to 220' set cementing plug and
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Les F. Massey
Conservation Division Agent