

State of Kansas



State Corporation Commission
CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

AUG 31 1967
CONSERVATION DIVISION
WICHITA, KANSAS

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

August 19, 1967

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Noel Knight of Knight Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Knight guarantees payment of the plugging fee.

Operator's full Name: Home-Stake Production Company

Complete Address: Philtower Bldg., Tulsa, Oklahoma 74103

Lease Name: Seedle "A" Well No. W-9

Location: NE SW NW Sec. 16 Twp. 24 Rge. 4 (E) (W) X

County Reno Total Depth 3381' Oil Well

Gas Well Input Well X SWD Well D & A Lost Hole

Mr. Knight was instructed to plug the well as follows:

Fill hole with sand to 3300' and cement with 3 sacks.

Fill hole with mud to 210'. Set rock bridge from 210' to 200' and

cement hole with 25 sacks. Fill hole with mud to 30'. Set rock

bridge from 30' to 20' and cap hole with 10 sacks cement.

Very truly yours,

Conservation Division Agent