



15135 207376000

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
APR 27 1973  
4-27-73  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Steincamp of Strata Drlg. has this

date requested permission to plug the following described well:

Mr. Steincamp guarantees payment of the plugging fee.

Operator's full Name: Dunigan Operating Co., Inc.

Complete Address: Box 2 Chanute, Ks.

Lease Name: Gerhardt Well No. 1

Location: NW SE Sec. 7 Twp. 17 Rge. (E)(W) 23

County: Ness Total Depth 4550' Oil Well       

Gas Well        Input Well        SWD Well        D & A XX Lost Hole       

Mr. Steincamp was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 750' and displace

70 sk cmt thru drill pipe. Heavy mud to 300' set cementing plug and

displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Eric J. Murray  
Conservation Division Agent