



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

AUG 27 1964
8-27-64
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Bill Walker of Rains & Williamson has this

date requested permission to plug the following described well:

Mr. Rains & Williamson guarantees payment of the plugging fee.

Operator's full Name: Rains & Williamson

Complete Address: 1425 Wichita Plaza Wichita, Kans

Lease Name: Ryan Well No. 1

Location: CNE SE Sec. 14 Twp. 17 Rge. (E) (W) 23

County Ness Total Depth 4520 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. was instructed to plug the well as follows:

8 5/8" 410' circulated with cement.

Circulated hole with heavy mud, set plug at 410', displaced 20 sax
cement through drill pipe, heavy mud to 180', set plug and displaced
20 sax cement through drill pipe, heavy mud to 35', set plug, hulls
and filled to bottom cellar with cement.

Very truly yours,

Eldon Perry
Conservation Division Agent