



15:35-20523-0000

ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 12:23:71
 DEC 23 1971
 CONSERVATION DIVISION
 Wichita, Kansas

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Coldwater of Alpine Drlg. has this date requested permission to plug the following described well:

Mr. Coldwater guarantees payment of the plugging fee.

Operator's full Name: Alpine Drlg., Co.

Complete Address: 800 Bitting Bldg., Wichita, Ks.

Lease Name: Anspaugh Well No. 1

Location: C NE SE Sec. 19 Twp. 17 Rge. (E)(W) 23

County: Ness Total Depth 4468' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Coldwater was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 700' and displace

70 sk cmt thru drill pipe. Heavy mud to 270' set cementing plug and

displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Geo F. Mansup
 Conservation Division Agent