

State of Kansas



15-185-00718-00-01

FORM - CP-2  
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor  
RICHARD C. BYRD Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

JUL 3 1963  
7-3-63  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Ed Walker of Garvey Drilling Co. has this date requested permission to plug the following described well:

Mr. Walker guarantees payment of the plugging fee.

Operator's full Name: Petroleum Inc.

Complete Address: 352 N. Broadway, Wichita, Kansas

Lease Name: Harter "B" Well No. # 1

Location: SW NW SW Sec. 9 Twp. 21 Rge. 13 (E) (W) W

County Stafford Total Depth 3689 Oil Well         

Gas Well          Input Well          SWD Well          D & A X Lost Hole         

Mr. Walker was instructed to plug the well as follows:

200' of 8 5/8" surface pipe, cement circulated with 175  
sacks. Fill hole with mud to 220', 1st cementing plug,  
1 sack hulls, cement with 20 sacks. Fill hole with mud  
to 40', 2nd cementing plug, 1 sack hulls, cement with 10  
sacks to base cellar. Bridge and cement rat hole with 2  
sacks.

Very truly yours,

Archie Elving  
Conservation Division Agent