

State of Kansas



15-135-30223-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECORDED
STATE CORPORATION COMMISSION
SEP 28 1964
09-23-1964
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Rowe of Slawson Drlg. Co. has this
date requested permission to plug the following described well:

Mr. Rowe guarantees payment of the plugging fee.

Operator's full Name: Donald C. Slawson

Complete Address: 408 One Twenty Building, Wichita, Kansas

Lease Name: Goatley "B" Well No. 1

Location: C SE NW Sec. 7 Twp. 19 Rge. 21 (E)(W) X

County Ness Total Depth 4406' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Rowe was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 540' and
Displace 30 sc cement thru drill pipe. Heavy mud to 320' set cementing
plug and displace 20 sc cement thru drill pipe. Heavy mud to 40' set
cementing plug, 1/3 sc hulls and 10 sc cement to base of celler.
Plug rat hole with 2 sc cement.

Very truly yours,

Frank Massey
Conservation Division Agent