

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-30062-00-00
Spot: NWSWNE Sec/Twnshp/Rge: 30-19S-21W
1874 feet from N Section Line, 2086 feet from E Section Line
Lease/Unit Name: MOORE-B Well Number: 5
County: NESS Total Vertical Depth: 4405 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: BOX 783188 8100 E 22ND ST. N. #700
WICHITA, KS 67278

Conductor Pipe: Size feet: 9 1/4 3.16
Surface Casing: Size 8.625 feet: 517 WITH 275 SX CMT
Production: Size 4.5 feet: 4404 WITH 100 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 10/07/2002 3:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: BENNIE DILLS Company: RITCHIE EXPLORATION Phone: (316) 691-9500

Proposed
Plugging
Method:

FILL CASING WITH CEMENT AND CIRCULAT TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: RICHARD LACEY Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 10/07/2002 3:40 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

PBTD 4404'. PERFS AT 4388-4392'. SQUEEZED CASING LEAK AT 967-1186' WITH 645 SX CMT. CUT WELL HEAD OFF. RAN MEASURING LINE DOWN BACKSIDE. SOLID CMT AT 80' FROM SURFACE. HOOK ONTO 4 1/2" CASING AND PUMPED 500# HULLS & 265 SX CMT DOWN 4 1/2" CASING. MAXIMUM PRESSURE 700#. SHUT IN PRESSURE 200#. WENT OVER TOP WITH 10 SX DOWN BACKSIDE. FILLED TO SURFACE. 10/08/02: CHECKED CMT TOP. CMT DOWN 500'. TOPPED OFF WITH 20 SX CMT.

RECEIVED

10-17-2002
OCT 17 2002

KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01

Signed

(TECHNICIAN)

INVOICE # OCT 09 2002

DATE 10-18-02

INV. NO. 2003060654

Form OK-27