

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-19004-00-00
Spot: NENENE Sec/Twnshp/Rge: 30-19S-21W
660 feet from N Section Line, 810 feet from E Section Line
Lease/Unit Name: MOORE B/P Well Number: 6
County: NESS Total Vertical Depth: 4467 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: BOX 783188 8100 E 22ND ST. N. #700
WICHITA, KS 67278

Conductor Pipe: Size feet: 145.18
Surface Casing: Size 8.625 feet: 508 WITH 275 SX CMT
Production: Size 4.5 feet: 4466 WITH 150 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 10/08/2002 3:40 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: BENNIE DILLS Company: RITCHIE EXPLORATION Phone: (316) 691-9500

Proposed Plugging Method: SAND TO 4375' & 4 SX CMT. PLUG AT 730' WITH 50 SX CMT. PLUG AT 520' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 10/08/2002 5:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PBTD 4450'. PERFS AT 4436-4445'. SANDED TO 4360' WITH 4 SX CMT. 1ST PLUG AT 730' WITH 50 SX CMT. 2ND PLUG AT 520' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

RECEIVED
10-17-2002
OCT 17 2002
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 910' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed Michael Maier
(TECHNICIAN)

INVOICE OCT 09 2002

DATE 10-18-02 MP

INV. NO. 2003060654

Form CP-2/3