

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-173-20005-00-01
Spot: SWNE Sec/Twnshp/Rge: 34-25S-1E
990 feet from N Section Line, 990 feet from E Section Line
Lease Name: HALEY Well #: 2 OWWO
County: SEDGWICK Total Vertical Depth: 3428 feet

Operator License No.: 5446
Op Name: GILES, BENJAMIN M.
Address: 346 S. LULU
WICHITA, KS 67211

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	4.5	3407		200 SX
PROD	5.5	3426		225 SX
SURF	8.625	200		175 SX
T1	2.875	2682		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/26/2012 5:00 PM
Plug Co. License No.: 34231 Plug Co. Name: M & S WELL SERVICE, LLC
Proposal Revd. from: DUSTY Company: M & S WELL SERVICE, LLC Phone: (316) 655-7542

Proposed Plugging Method: SAND BACK OPEN HOLE TO 3370' AND CAP WITH 4 SX CMT, PERFORATE 4 1/2 @ 250' AND CIRCULATE CMT TO SURFACE. USE 60/40 POS MIX W/4%/GEL.

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/25/2012 2:00 PM KCC Agent: DAN FOX

Actual Plugging Report:

PLUGGING CONTRACTOR DUMPED 60 GAL. OF SAND DOWN 4 1/2" CASING AND CAPPED WITH 5 SX OF CEMENT ON 7/25/12. I ARRIVED @ 11:00 AM AND WITNESSED CONTRACTOR TAG TOP OF CEMENT AT 3368' ON 7/26/2012. GRESSEL OIL SERVICES WAS ON SITE TO SHOOT PERFORATIONS 4 SHOTS/1FT. @ 255' CIRCULATED 120 SX TO SURFACE. CEMENT TICKET #38033. RECHECKED TOP PLUG AFTER A FEW DAYS TO VERIFY TOP PLUG HAS NOT SLIPPED.

Perfs:

Top	Bot	Thru	Comments
255	256	CSG	

Remarks: WELL WAS PLUGGED DUE TO NON-COMPLIANCE LETTER OF NON-PRODUCTION FROM DISTRICT 2.

Plugged through: TBG

District: 02

Signed

Daniel J. The
8/02/12 (TECHNICIAN)
RECEIVED

JUL 31 2012

Form CP-2/3

124
KCC WICHITA