

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-083-21814-00-00
Spot: NWSWNWSE Sec/Twnshp/Rge: 25-22S-23W
1757 feet from S Section Line, 2627 feet from E Section Line
Lease Name: O'BRATE-STEIN Well #: 1-25
County: HODGEMAN Total Vertical Depth: 4610 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	224		WITH 150 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 07/21/2012 9:30 AM
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.
Proposal Rcvd. from: KEN MCGUIRE Company: DUKE DRILLING CO., INC. Phone: (316) 267-1331

Proposed Plugging Method: 1ST PLUG AT 1550' WITH 50 SX CMT. 2ND PLUG AT 630' WITH 60 SX CMT. 3RD PLUG AT 300' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: NONE
Date/Time Plugging Completed: 07/21/2012 11:30 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

1ST PLUG AT 1550' WITH 50 SX CMT. 2ND PLUG AT 630' WITH 60 SX CMT. 3RD PLUG AT 300' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

RECEIVED
JUL 30 2012
KCC WICHITA

District: 01

Signed Richard W. Lacey
8/20/12 (TECHNICIAN)

RECEIVED
JUL 25 2012
KCC DODGE CITY

any