

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-21354-00-01
Spot: SWSENWSW Sec/Twnshp/Rge: 22-23S-34W
1649 feet from S Section Line, 4345 feet from E Section Line
Lease Name: SEQUOYAH MORROW UNIT Well #: 304W
County: FINNEY Total Vertical Depth: 4905 feet

Operator License No.: 5447
Op Name: OXY USA INC.
Address: 5 E GREENWAY PLZ PO BOX 27570
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4650		WITH 2 SX CMT
CIBP		4716		
DVT		2977		
PROD	5.5	4905	0	WITH 775 SX CMT
SURF	8.625	1939		WITH 530 SX CMT

Well Type: EOR UIC Docket No: E27836.4 Date/Time to Plug: 07/19/2012 2:00 PM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: JOHN SCHOOLCRAFT Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: CIBP @ 4650' WITH 2 SX CMT. PLUG AT 3000' WITH 20 SX CMT. PLUG AT 1980' WITH 30 SX CMT. PLUG AT 1080' WITH 30 SX CMT. PLUG AT 40' WITH 5 SX CMT. CHECK BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: NONE
Date/Time Plugging Completed: 07/20/2012 1:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

CIBP @ 4650' WITH 2 SX CMT. PUMP 150# HULLS AT 3200'. 1ST PLUG AT 3000' WITH 20 SX CMT. SDON. 7/20/12: TAG TOP OF CMT PLUG AT 2804'. 2ND PLUG AT 1980' WITH 30 SX CMT. 3RD PLUG AT 1080' WITH 30 SX CMT. 4TH PLUG AT 40' WITH 5 SX CMT. PUMP 10 SX CMT DOWN ANNULUS TO 500#.

Perfs:

Top	Bot	Thru	Comments
4769	4772		
4744	4748		
4736	4740		
4720	4726		
4694	4700		

RECEIVED
JUL 30 2012
KCC WICHITA

Remarks: **COMPLIANCE ISSUE: FAILED MIT** USED COMMON CEMENT BY SARGENT & LILLARD.

Plugged through: TBG

District: 01

RECEIVED

JUL 23 2012

KCC DODGE CITY

Signed

Michael Maier
(TECHNICIAN)

Form CP-2/3

Handwritten initials