

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-01150-00-01
Spot: NESENW Sec/Twnshp/Rge: 16-7S-22W
3630 feet from S Section Line, 2970 feet from E Section Line
Lease Name: WORCESTER G16 Well #: 1
County: GRAHAM Total Vertical Depth: 3900 feet

Operator License No.: 30259
Op Name: WERTH, ANDY DBA WERTH EXPLORA
Address: 1308 SCHWALLER AVE
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3879		
SURF	8.625	151		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/13/2012 9:00 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed CIBP # 3615'
Plugging Ordered 675 sx 60/40 pozminx 4% gel cement w/800 # hulls.
Method: Perforations: 3588'-3589', 3472'-3475', and 3460'-3462'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/13/2012 5:15 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3500'. Pumped 100 sx cement w/300 # hulls.
Pulled tubing to 2502'. Pumped 100 sx cementw/350 # hulls.
Pulled tubing to 1517'. Pumped 160 sx cement w/150 # hulls.
Pulled tubing out. Pumped 30 sx cement down casing. Casing full.
Tied onto back side. Pumped 145 sx and 150 # hulls.
Ran out of cement. Had to go on 5 hour trip for more cement to great Bend, KS.


Perfs:

Top	Bot	Thru	Comments
3796	3800		
3742	3747		
3716	3718		
3588	3594		
3536	3544		

Remarks: COPELAND ACID AND CEMENT TICKET # 39799

Plugged through: TBG

District: 04

Signed  (TECHNICIAN) CM

JUL 24 2012

RECEIVED 8/2/12
JUL 30 2012
7-30-12
KCC WICHITA