

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-069-20146-00-01
Spot: SWSW Sec/Twnshp/Rge: 30-25S-28W
696 feet from S Section Line, 662 feet from W Section Line
Lease Name: IRISK Well #: 1 OWWO
County: GRAY Total Vertical Depth: 4990 feet

Operator License No.: 34472
Op Name: SUNFLOWER ENERGY, LLC
Address: 10801 MASTIN, STE 920
OVERLAND PARK, KS 66210

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4821	0	WITH 375 SX CMT
SURF	8.625	411		WITH 160 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 07/24/2012 8:30 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: DAVID E. RICE Company: SUNFLOWER ENERGY Phone: (620) 624-0156

Proposed Plugging Method: PUMP 30 SX CMT & 150# HULLS AT 4760' THRU TBG. PULL TBG TO 2000' & LOAD HOLE. PLUG AT 2000' WITH 25 SX CMT. PLUG AT 950' WITH 25 SX CMT. PLUG AT 450'-0' WITH 45 SX CMT. BRING 50 EXTRA SX FOR ANNULUS.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/24/2012 1:25 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SQUEEZED AT 1000'. CMT TO SURFACE. 1ST PLUG AT 4769' WITH 30 SX CMT & 150# HULLS. 2ND PLUG AT 2012', LOAD HOLE & 25 SX CMT. 3RD PLUG AT 944' WITH 25 SX CMT. 4TH PLUG AT 463'. CIRCULATED CMT TO SURFACE WITH 45 SX CMT. BACKSIDE WAS FULL.

Perfs:

Top	Bot	Thru	Comments
4764	4767		
1000	1001		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

RECEIVED

JUL 30 2012

KCC WICHITA

District: 01

Signed Eric MacLaren
8/02/12 (TECHNICIAN)

RECEIVED
JUL 25 2012
KCC DODGE CITY

Handwritten initials