

TO:
STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-019-19856-00-00
Spot: SESENWNW Sec/Twnshp/Rge: 15-34S-12E
4093 feet from S Section Line, 4125 feet from E Section Line
Lease Name: WINDERS Well #: 9
County: CHAUTAUQUA Total Vertical Depth: 1060 feet

Operator License No.: 32619
Op Name: EXCEL OIL & GAS L.L.C.
Address: PO BOX 68
BUCYRUS, KS 66013

<u>String</u>	<u>Size</u>	<u>Depth (ft)</u>	<u>Pulled (ft)</u>	<u>Comment</u>
PROD	6	1060		
SURF	10	20		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/02/2012 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: MATT JONES Company: _____ Phone: (620) 725-3636

Proposed Plugging Method: SURFACE CEMENT AND PRODUCTION CASING CEMENT UNKNOWN. RUN 1" TO TD. GEL HOLE. SPOT 20 SX OF CEMENT ON BOTTOM. PULL OUT AND PERFORATE @ 700' AND 350'. RUN 1" BACK IN AND PLUG W/ 20 SX @ 700'. PULL UP TO 350' AND CEMENT TO SURFACE.

Plugging Proposal Received By: DUANE SIMS WitnessType: PARTIAL
Date/Time Plugging Completed 01/03/2012 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Ran 1" to 950' gelled hole and spotted 20 sack plug. Pulled 1" and perforated casing at 700' and 350'. Ran 1" back into 700' and spotted 20 sack plug. Pulled up to 350' and circulated cement to surface. Pulled 1" and topped well off. A total of 141 sacks of cement were used to plug this well.

RECEIVED

JUL 20 2012 DAS

KCC Chanute Dist. #3

Remarks:

Plugged through: TBG

District: 03

Signed

[Signature]
8/02/12
TECHNICIAN)
RECEIVED
JUL 27 2012
KCC WICHITA