

TO:  
STATE CORPORATION COMMISSIO  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 6720

API Well Number: 15-049-22565-00-00  
Spot: NWSWSESE Sec/Twnshp/Rge: 25-28S-9E  
526 feet from S Section Line, 1300 feet from E Section Line  
Lease Name: ECK Well #: 16-25  
County: ELK Total Vertical Depth: 2630 feet

Operator License No.: 33365  
Op Name: LAYNE ENERGY OPERATING, LLC  
Address: PO BOX 160  
SYCAMORE, KS 67363

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	40		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/14/2012 12:00 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: \_\_\_\_\_ Company: \_\_\_\_\_ Phone: \_\_\_\_\_

Proposed Plugging Method: 50' plug at TD, 50' plug at 2300', 50' plug at 1300' and 500' to surface.

Plugging Proposal Received By: DUANE SIMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed 05/14/2012 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Ran 2" tubing to 2628' gelled hole and spotted 15 sack plug. Pulled up to 2304' and spotted 15 sack plug. Pulled up to 1302' and spotted 15 sack plug. Pulled up to 501' and circulated cement to surface. Pulled 2" and topped well off. A total of 230 sacks of 60/40 pozmix cement were used to plug this well.

RECEIVED

JUL 24 2012 DAS


KCC Chanute Dist. #3

Remarks:

Plugged through: TBG

District: 03

Signed

  
(TECHNICIAN)

RECEIVED

JUL 27 2012

KCC WICHITA