

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 125-45

LOCATION SE-SW-SE

SEC. 17 TWP. 11 RGE. 18-16

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Richards

Operator A.H.B. Drilling Co Address 705 - Petroleum Bldg - Wichita

Field _____ County Ellis

Total Depth 3471 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 3/8 - 1027 ft. Circulated with cement from top to bottom - 5 1/2" casing set at 3465 & cemented with 100 sacks cement - Perforated at 3178 & tested - No Oil Set Plug & 6 sacks Cement 3175 ft - Shut off & recovered 2900 ft of 5 1/2" casing - Well flowing water from bottom of 8 3/8 casing - Sun Oil Well Cementing Co - Pumped in Plug & 200 Sacks Cement - & 500 ft of heavy mud on top - Plug stopped at 1030 ft - Surface Plug 20 ft below the surface & 6 sacks of cement filling hole to surface.
Carl Miller - Pipe Puller
Contractor

C. H. S. [Signature]
District Conservation Agent
Date 9-5-47

SEP 9 - 1947

PLUGGING
FILE SEC. 17-T-11-R-18W
BOOK PAGE 125 LINE 45