

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

051 - 03713 50001

API Number 15-OWWO-

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Robert R. Price Operating, Inc.

Complete Address P.O. Box 45442, Tulsa, Ok. 74145

Lease Name Fräbie "E" Well No. 1

Location NE NE SE Sec. 18 Twp. 11 Rge. 18 (East)(West)

County Ellis Total Depth 2196'

Abandoned Oil Well Gas Well Input Well SWD Well D&A XXXX

Other well as hereinafter indicated

Plugging Contractor Ranger Drilling Co., Inc.

Address 1003 Canterbury Rd., Hays, Ks. 67601

License No.

Operation Completed: Hour: 11:45 AM Day: 9 Month: 7 Year: 19 82

Plugging Operations attended by Agent?: All Part None T

The above well was plugged as follows:

OWWO Found 1st plug at 18' from surface, 2nd plug at 94', 3rd plug at 1300', Old bid in hole had to plug well.

8 5/8"-92' S.P. cuc.w/common cement.

Ordered 140 sacks 50/50 posmix-4% Gel.-3% Cal.Cl. 7 8 5/8" plug.

Spot w/drill stem w/heavy mud between all plugs.

1st plug @ 720' w/80 sacks cement.

2nd plug @ 150' w/40 sacks cement.

3rd plug-solid bridge of hulls & plug @ 40' w/10 sacks cement.

Circulate 10 sacks in rat hole.

Amount of Surface Casing: 92' of 8 5/8"

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Out plugging well on location in Ellis Co. 36-11-20w

RECEIVED
STATE CORPORATION COMMISSION

JUL 19 1982

CONSERVATION DIVISION
Wichita, Kansas

Signed: [Signature]
Conservation Division Agent

DATE 7-23-82

WV NO. 728-W