

KANSAS

Form CP-3
Rev. 6-4-68

P

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

OCT 12 1976

CONSERVATION DIVISION
STATE OF KANSAS

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 051 - 21,219 - 0000 (of this well)

Operator's Full Name Robert R. Price

Complete Address Box 45442, Tulsa, Oklahoma

Lease Name Frisbie Well No. 1

Location NW NW NE Sec. 18 Twp. 11 Rge. (E) (W) 18

County Ellis Total Depth 3516'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Allen Drlg.

Address Hosington, Kansas License No.

Operation Completed: Hour 5 P Day 10 Month 10 Year 1976

The above well was plugged as follows:

RTD 3516' 8 5/8 csg set 258' cwc Plg. Mat. 50-50 poz 2% total gel.

Gunned pits, circulated heavy mud, set 50 sk cmt plug at 420' thru drill pipe.

Heavy mud to 240' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Murray
Well Plugging Supervisor

DATE 10-12-76

INV. NO. 3973-W