

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-051--23,018-0000

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name National Development Company

Complete Address 833 N. Vaco, Wichita, Kansas 67203

Lease Name Frisbie Well No. #1

Location N: SE NW Sec. 19 Twp. 11 Rge. 18 (East) (West)

County Ellis Total Depth 2585'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Duke Drilling Company, Inc.

Address 818 Main, Box 822, Great Bend, Kansas 67530 License No. _____

Operation Completed: Hour: 12:00AM Day: 29th Month: May Year: 19 82

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

8 5/8" - 258' s.p. cuc. w/100 sacks 60/100 posmix-2% Gel.-3% Cal. Cl.

Ordered 120 sacks 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" plug.

Spot with drill stem with heavy mud between all plugs.

1st plug @ 750' w/70 sacks cement

2nd plug @ 270' w/10 sacks cement

3rd plug-solid bridge of hulls and plug @ 40' w/10 sacks of cement

Circulate with 10 sacks of cement in rat hole.

Amount of Surface Casing: 258' of 8 5/8"

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Muddy Roads into rotary could only be traveled by a 4-wheel vehicle.

RECEIVED
STATE CORPORATION COMMISSION

Signed: [Signature] JUN - 2 1982
Conservation Division Agent
Wichita, Kansas

6-3-82
362-W

STATE CORPORATION COMMISSION
 CONSERVATION DIVISION
 200 Colorado, Derby Bldg.
 Wichita, Kansas 67202-1286

INVOICE and WELL PLUGGING AUTHORITY

June 3, 1982

INVOICE NUMBER: 362-W

TO: National Development Company
833 N. Waco
Wichita, KS 67203

PLUGGING ASSESSMENT AS FOLLOWS:

Frisbie #1
 NW SE NW, Sec. 19-11S-18W
 Ellis \$116.51
 T.D. 3585'

NOTE: We also need the following before our file is completed:


 x
 x Well Plugging Record (CP-4)
 x Well Log
 x Well Plugging Application (CP-1)

WELL PLUGGING AUTHORITY

Gentlemen:

This is your authority to plug the above subject well in accordance with the rules and regulations of the state corporation commission.

This authority is void after ninety (90) days from the above date.


 Administrator

Mr. Gil Scheck, 2202 Canterbury Rd., Hays, KS., 67601, (913)628-2600

is hereby assigned to supervise the plugging of the above mentioned well.