

DISTRICT CONSERVATION AGENT'S REPORT

W

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION ~~SE-71E~~ SE SE NE

SEC. 19 TWP. 11 RGE. 18W

Dry Hole X Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Miller

Operator Shelly Oil Co Address Box #309 - Hutchinson - Kans

Field \_\_\_\_\_ County Ellis

Total Depth 3670 Feet.

(Describe briefly the manner in which the well was plugged)

Sucker Pipe 13 3/8 - 15 7/16 cemented all around  
8 3/4 casing 1392 ft. cemented with 530 sacks cement.  
30 sacks cement at bottom of hole - Plug &  
15 sacks at 1390 ft - Plug & 15 sacks cement  
at 175 ft - Sucker Plug 20 ft below this - plug  
& 10 sacks cement - Halliburton Oil Well Cementing  
Co. Pumped in all plugs & cement - Heavy Mud  
between all plugs - from  
top to bottom of hole

C. H. Stover  
District Conservation Agent

Date 8-24-47 8-26-47

**PLUGGING**  
FILE SEC 19 T 11 R 18W  
BOOK PAGE 128 LINE 39

X