

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

STATE CORPORATION COMMISSION
MAR 28 1960
CONSERVATION DIVISION
Wichita, Kansas

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Ellis
Location NW NW NW Sec. 27 Twp. 11 Rge. 18 (E) (W) _____
Name of Field: _____ Total Depth: 3526

I have this date completed supervision of plugging of:

Lease Name: Henderson Well No. G-1

Operator's Full Name: Morganstern & Specter

Complete Address: Russell, Kans

Plugging Contractor: Knight Casing Pulling Co

Address: Chsae, Kans License No. 436

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other Well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes ___ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 4PM Day 17 Month 3 Year 60

The above well was plugged as follows:

8 5/8" 1248' circulated with cement - 5 1/2" 3515' with 125 sax cement -

5 1/2" squeezed and circulated with cement to 0' - No pipe recovery.

PB to 3472' - perforated 3244' - filled with sand to 3230', set 4 sax

cement with dump bailer - pumped hole full mud (open end) gel mud to

500' (24 sax mud), filled hole with cement 500' to 0', pumped open end.

Mudding and cementing by Knight Casing Pulling Co's pump truck.

Reviewed: J. Lewis Brock

Signed: [Signature]
Conservation Division Agent

Remarks:

INVOICED

DATE 3/29/60

INV. NO. 1134-W