

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

STAT. ...
FEB 4 1960
CONSERVATION DIVISION
Wichita, Kansas

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Ellis
Location NW NW SW Sec. 27 Twp. 11 Rge. 18 (E) (W) _____
Name of Field: _____ Total Depth: 3619

I have this date completed supervision of plugging of:

Lease Name: Henderson Well No. H-1

Operator's Full Name: Morganstern & Specter

Complete Address: Box 661 Russell, Kans

Plugging Contractor: Knight Casing Pulling Co

Address: Chase, Kans License No. 436

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other Well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes ___ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 7PM Day 30 Month 1 Year 60

The above well was plugged as follows:

8 5/8" 1304' circulated with cement - 5 1/2" 3607' with 125 sax cement.
Filled with sand to 3590', set 4 sax cement with dump bailer, pulled
2800' 5 1/2" to 600', circulated hole with heavy mud through 5 1/2" at 600',
(35 sax Gel), displaced 20 sax cement through 5 1/2" at 600', heavy mud to
200', displaced 20 sax cement through 5 1/2" at 200', heavy mud to 35',
set rock bridge and 10 sax cement to 0'.
Mudding and cementing by Knight Casing Pulling pump truck.

Reviewed: J. Lewis Brock

Signed: Eason Perry
Conservation Division Agent

Remarks:

INVOICED
DATE 2/9/60
INV. NO. 938w