

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 1 1959
CONSERVATION DIVISION
Wichita, Kansas
R

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 19-36 County: Ellis

Location: SE NW NW Sec. 27 Twp. 11 Rge. 18 (E) (W)

Name of Field: _____ Total Depth: 3614

I have this date completed supervision of plugging of:

Lease Name: Henderson Well No. G-6

Operator's Full Name: Don Brown

Complete Address: 2311 Liberty Bank Bldg Oklahoma City, Okla

Plugging Contractor: West Supply Co

Address: Chase, Kans License No. 14

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 6PM Day 21 Month 3 Year 59

The above well was plugged as follows:

8 5/8" at 1365' circulated with cement - 5 1/2" 3606' with 100 sax cement behind.

Filled with sand to 3595', set 4 sax cement with dump bailer, pulled 2960' 5 1/2" to 600', circulated hole with heavy mud (Gel) through 5 1/2", displaced 25 sax cement through 5 1/2" at 600', heavy mud to 220', displaced 20 sax cement through 5 1/2" at 220', heavy mud to 35', set bridge and 10 sax cement to bottom cellar.

Mudding and cementing by West Supply Co's pump truck.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

PLUGGING
FILE SEC. 27 T. 11 R. 18W
BOOK PAGE 19 LINE 36