

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
APR 1 1959  
CONSERVATION DIVISION  
Wichita, Kansas

R

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. 19-35 County: Ellis  
Location: SW NE NW Sec. 27 Twp. 11 Rge. 18 (E) (W)  
Name of Field: \_\_\_\_\_ Total Depth: 3630

I have this date completed supervision of plugging of:

Lease Name: Henderson Well No. G-5  
Operator's Full Name: Don Brown  
Complete Address: 2311 Liberty Bk Bldg Oklahoma City, Okla  
Plugging Contractor: West Supply Co  
Address: Chase, Kans License No. 14

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_  
Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes \_\_\_\_\_ No   
If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 11AM Day 27 Month 3 Year 59

The above well was plugged as follows:

8 5/8" at 1382' circulated with 650 sax cement - 5 1/2" 3620' with 100 sax cement behind.

Filled hole with sand to 3610', set 4 sax cement with dump bailer, pulled 2970' 5 1/2" to 600', circulated hole with heavy mud ( Gel ) through 5 1/2" at 600', displaced 25 sax cement through 5 1/2" at 600', heavy mud to 210', displaced 20 sax cement through 5 1/2" at 210', heavy mud to 35', set rock and 10 sax cement to bottom cellar.

Mudding and cementing by West Supply Co's pump truck.

Signed: [Signature]  
Conservation Division Agent

Reviewed: [Signature]  
Field Supervisor

Remarks:

PLUGGING  
FILE SEC. 27 T. 11 R. 18W  
BOOK PAGE 19 LINE 35