

*M*  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 12 1969  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Champlin Petroleum Co.  
Complete Address Box 308 Ellinwood, Kansas  
Lease Name Johnson "L" Well No. 1  
Location C S/2 NE SE Sec. 32 Twp. 11 Rge. (E) (W) 18  
County Ellis Total Depth 3300'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX  
Other well as hereafter indicated         
Plugging Contractor Red Tiger Drlg.  
Address Wichita, Kansas License No.         
Operation Completed: Hour 10:45A Day 8 Month 8 Year 1969

The above well was plugged as follows:

RTD 3300' 8 5/8 csg set at 215' cwc Cmt. Lat. 50-50 poz cmt 11/63 total gel.  
Gunned pits, circulated heavy mud, set cementing plug at 660' and displaced 70 sk cmt  
thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sk cmt thru  
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base  
of cellar.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**  
DATE 8/12/69  
INV. NO. 287-4

Signed: Leo F. Massey  
Well Plugging Supervisor