

R

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 2 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Champlin Petroleum Company
Complete Address 2915 N. Lincoln Oklahoma City, Oklahoma 73105
Lease Name Johnson "M" Well No. 2
Location SE SW NW NW Sec. 32 Twp. 11 Rge. (E) (W) 18
County Ellis Total Depth 3602'
Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Knight Casing Pulling
Address Box 405 Chase, Kansas 67524 License No. 436
Operation Completed: Hour 2 P Day 30 Month 10 Year 1973

The above well was plugged as follows:

Total Depth 3602' 8 5/8 csg set at 1236' cwo
4 1/2 csg set at 3585' cw 225 sk cmt.
PBTD 3557' with top perf. (3364)
Set 4 1/2 wood plug at 3300' -- poured 25' sd & dumped 3 sk cmt W/dump bailer. (3250-3300)
Cutoff and recovered 2500' of 4 1/2 csg.
Filled 8 5/8 csg W/mud to 550' --rock & sand bridge (535-550)
Dumped 7 1/2 yds readymix cem from 535 to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Massup
Well Plugging Supervisor

DATE 11/2/73

INV. NO. 8098-W