

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

SEP 8 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Shell Oil Co
Complete Address: 1200 1st Natl Bk Bldg Oklahoma, City, Okla
Lease Name Johnson Well No. C-1
Location NW NW NW Sec. 32 Twp. 11 Rge. (E) (W) 18
County Ellis Total Depth 3596
Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling

Address: Great Bend, Kans License No. 49

Operation Completed: Hour 11AM Day 3 Month 9 Year 64

The Above well was plugged as follows:

8 5/8" 1240' circulated with cement - 5 1/2" 3590' top cement at 3042'
Perf 3315' - sand back to 3300', set 4 sax cement with dump bailer.

Pulled 2000' 5 1/2" to 1750' - circulated hole with heavy gel mud through
5 1/2" (20 sax Gel), displaced 20 sax cement through 5 1/2" at 580' - heavy
mud to 200', displaced 20 sax cement through 5 1/2" at 200', heavy mud to
20' - cement 20' to 18 0'

Mudding and cementing by Halliburton Co.

I hereby certify that the above well was plugged as herein stated.

DATE 9/8/64
INV. NO. 9483-W

Signed: [Signature]
Well Plugging Supervisor