



State Corporation Commission
CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

DEC 27 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Linemiller of Abercrombie Mfg Co. has this date requested permission to plug the following described well:

Mr. Linemiller guarantees payment of the plugging fee.

Operator's full Name: Rain & Williamson

Complete Address: 1425 - Wichita Plaza - Wichita Kans.

Lease Name: Jensen Well No. 1

Location: Ne-Ne-Sw Sec. 34 Twp. 11 Rge. 19 (E) (W)

County Ellis Total Depth 3650 Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Linemiller was instructed to plug the well as follows:

Jett pitts circulate hole with heavy mud, set cementing plug at 540ft.
and displace 20 sax cement thru drill pipe, heavy mud to 230 ft.,
set plug and displace 20 sax cement, heavy mud to 40 ft., set
plug 1/2 sac hulls and 10 sax cement, cementing to base of cellar.

Very truly yours,

Gilbert P. Leiker
Gilbert P. Leiker
Conservation Division Agent