



ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 E. EDWARD JOHNSON Gen. Counsel

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. - 212 N. Market  
 WICHITA, KANSAS 67202

**VERBAL PERMIT FORM**  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION  
 JUN 3 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Burt of Burt Drlg. has this

date requested permission to plug the following described well:

Mr. Burt guarantees payment of the plugging fee.

Operator's full Name: Hummom Oil, Inc.,

Complete Address: 821 Union National Bldg., Wichita, Kansas

Lease Name: Jensen Well No. 1

Location: SW NE SE Sec. 34 Twp. 11 Rge. 19 (E)(W) X

County: Ellis Total Depth 3678' Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Burt was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 800' and displace  
70 sc cement thru drill pipe. Heavy mud to 180' set cementing plug and  
displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing  
plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole  
with 2 sc cement.

Very truly yours,

Ben F. Messer  
 Conservation Division Agent