



15051-213 23132-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

RECEIVED
STATE CORPORATION COMMISSION
SEP 09 1982
CONSERVATION DIVISION
Wichita, Kansas
VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Bernie Meyer of Murphy Drilling Co. ^{W/C # 16} has this date requested permission to plug the following described well:

Operator's Full Name: Don Pratt Oil Operations

Complete Address: 1011 Fort, Hays, Kans. 67601

Lease Name: Dale Solomon Well No. "B" # 5-31

Location: NW-NE-NE Sec. 31 Twp. 11 Rge. 19 (E) (W)

County: Ellis Total Depth: 3704 FE

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Meyer was instructed to plug the well as follows:

8 5/8" - 165 FE SP. CUL. w/ 145ST Common Quick Set (altered cut)
Order 140ST 50% Pozmix 4% Gel-3% Ca-Cl. -> 8 5/8" Plug
spot with Drill Stem - with heavy mud between cell plugs.
1ST Plug @ 870 FE w/ 80ST Cmt.
2ND Plug @ 240 FE w/ 40ST Cmt.
3RD Plug -> Solid Bridge @ 40 FE w/ 10ST Cmt.
10ST In Pat Hole very truly yours, (By altered cut)

Superior Schmidt
Conservation Division Agent