



15:051-23180-0000

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

STATE RECEIVED
CONSERVATION DIVISION
WICHITA, KANSAS
OCT 07 1982

VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Bernis Meyers of Murfin Drilling Co. has this

date requested permission to plug the following described well:

Operator's Full Name: Pratt Don E. Oil Operations

Complete Address: P.O. Box 370, Hays, Ks 67601 # 6114

Lease Name: dail Solomon "B." Well No. 8-31

Location: SE NW NE Sec. 31 Twp. 11 Rge. 19 (E) (W)

County: Ellis Total Depth: 3744'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Meyers was instructed to plug the well as follows:

8 5/8" - 1168' SP. case w/ 145 sacks Common - 2% Gel. - 3% Cal. U.

Ordered 140 sacks 50 posmix - 4% Gel - 3% Cal. U. + 8 5/8" plug. Spot w/ drill stem

w/ heavy mud between all plugs. 1st plug C 720' w/ 80 sacks

2nd plug C 200' w/ 40 sacks

3rd plug - Solid bridge of bulls + plug C 40' w/ 10 sacks

Circulate 10 sacks in rat hole.

Very truly yours,

Scott J. Schube
Conservation Division Agent