

State of Kansas



15-051-21576-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

OCT 23 1978

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Augustine of Murfin Drlg. has this

date requested permission to plug the following described well:

Mr. Augustine guarantees payment of the plugging fee.

Operator's full Name: Don E. Pratt

Complete Address: Box 370, Hays, Ks.

Lease Name: Dale Solomon Well No. 8-31

Location: 1320' FNL & 440' FWL SE/4 Sec. 31 Twp. 11 Rge. (E)(W) 19

County: Ellis Total Depth 3785' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Augustine was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 70 sk cmt plug at 600' thru drill
pipe. Heavy mud to 150' set 20 sk cmt plug thru drill pipe. Heavy
mud to 40' set solid bridge & 10 sk cmt plug to base of cellar.

Very truly yours,

Geo Massey
Conservation Division Agent