

1050330

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-22,648 -0000

SW SE NW, SEC. 13; T 19 S, R26 W/E
2310 feet from N SE Corner of HXX section line
1650 feet from W SE Corner of HXX section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6732

Lease Name Antenen Well # 1

Operator: Vicorp Energy, Inc.
Name & Address: 6200 S. Syracuse Way, Suite 125
Englewood, CO 80111

County Ness

Well Total Depth 4675 151.94 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 552

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor H-30 Drilling, Inc. License Number 5107

Address 251 North Water, Suite 10, Wichita, KS 67202

Company to plug at: Hour: 4:00 pm Day: 4 Month: September Year: 19 84

Plugging proposal received from Rick Davis

(company name) H-30 (phone) 316-263-2043

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1830' with 50 sx cement

2nd plug at 990' with 50 sx cement

3rd plug at 600' with 40 sx cement

4th plug solid bridge hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part X _____ None _____

Operations Completed: Hour: 5:15 pm Day: 4 Month: September Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1830' with 50 sx cement, 2nd plug at 990' with 50-

sx cement, 3rd plug at 600' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole

with 10 sx cement.

RECEIVED STATE CORPORATION COMMISSION

SEP 11 1984

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Sun

(If additional description is necessary, use BACK of this form.)

INVOICED

(If additional description is necessary, use BACK of this form.) observe this plugging.

DATE 9-19-84

Signed Richard W. Lacey SQ (TECHNICIAN)

INV. NO. 3720

9-4