

DEC 9 1988

070626

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-21,007-0000
SE SW NW, SEC. 2, T 19 S, R 24 W/E
2970 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6568

Lease Name Brandt Well # 1

Operator: Kaiser-Francis Oil Company

County Ness 140.89

Name & Address P.O. Box 21468

Well Total Depth 4335 feet

Tulsa, OK 74121-1468

Conductor Pipe: Size feet

Tulsa, OK 74121-1468

Surface Casing: Size 8 5/8 feet 247

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kaiser-Francis Oil Company License Number 6568

Address P.O. Box 21468, Tulsa, OK 74121-1468

Company to plug at: Hour: 9:30 a.m. Day: 9 Month: 12 Year: 19 88

Plugging proposal received from John Glenn

(company name) Kaiser-Francis Oil Company (phone) 316-564-3214

were: 4 1/2" at 4332' Perfs at 4229-46'

1st plug pump 300 lbs. hulls and 90 sx Econolight and plug to 870', perforate at 850',

2nd plug pump 100 sx in backside,

3rd plug pump 90 sx cement in 4 1/2".

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 12:15 p.m. Day: 9 Month: 12 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug pumped 300 lbs. hulls, 90 sx Thrifty Mix, and 4 1/2" wiper plug to 870', perforate at 850',

2nd plug pumped 90 sx 60/40 Pozmix 6% gel down 4 1/2" casing. Maximum pressure 200 psi and shut in 150 psi.

3rd plug pumped 100 sx 60/40 Pozmix 6% gel down 4 1/2" X 8 5/8" annulus. Maximum pressure 600 psi and shut in 600 psi.

RECEIVED STATE CORPORATION COMMISSION

Remarks: Used Thrifty Mix and 60/40 Pozmix 6% gel by B.J. Titan. No casing recovery.

(If additional description is necessary, use BACK of this form) DEC 13 1988

INVOICED

observe this plugging.

DATE 12-13-88

Signed Dan Goodrow CONSERVATION DIVISION (TECHNICIAN) Wichita, Kansas

INV. NO. 23341