

4-24-86

1 070174

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-23,023-0000

E/2 NW NW, SEC. 1, T 19 S, R 24 W/E
4620 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6455
Operator: Apache Drilling Co., Inc.
Name & Address: P. O. Box 454
Ness City, KS 67560

Lease Name Foos Well # 1
County Ness 142.68
Well Total Depth 4390 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 259

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Republic Drilling, Inc. License Number 9943
Address 310 W. Centra, # 214, Wichita, KS 67202

Company to plug at: Hour: 2:30 am Day: 24 Month: April Year: 19 86

Plugging proposal received from Mike Lanigan
(company name) Republic (phone) 316-264-0079

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2282'
Anhydrite 1530'

- 1st plug at the base of the Anhydrite with 50 sx cement
- 2nd plug 50' below the base of the Cheyenne Sand with 80 sx cement
- 3rd plug 30' below the base of the surface pipe with 40 sx cement
- 4th plug from 30' to surface with 10 sx cement
- 5th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 3:15 am Day: A2411 Month: April Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 1570' with 50 sx cement, 2nd plug at 780' with 80 sx cement,
Filled hole with mud after 2nd plug and swedged in 8 5/8". Will tag 2nd plug at a later
date and plug with tubing. Circulated rat hole with 15 sx cement.

Remarks: Used 60/40 Pozmix by **RECEIVED**
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE AUG - 6 1986
INV. NO. 14606

Signed Dan Gooden
(TECHNICIAN)

AUG 5 1986