

1 050197

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-22,553 - 0000

NW NW NE, SEC. 27, T 19 S, R 24

330 feet from N~~X~~ section line

1980 feet from ~~X~~W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5402

Lease Name Osborn Well # 1-27

Operator: Amber Exploration

County Ness

Name & Address 612 North Clay

Well Total Depth 4415 ~~4143.49~~ feet

Liberal, KS 67902

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 607

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Allen Drilling Company License Number 5418

Address P. O. Box 1389, Great Bend, KS 67530

Company to plug at: Hour: 8:00 pm Day: 21 Month: April Year: 1984

Plugging proposal received from Don Kern

(company name) Allen Drilling Company (phone) 316-793-5681

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1600' with 50 sx cement 2nd plug at 750' with 70 sx cement

3rd plug at 300' with 40 sx cement solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rathole with 15 sx cement

Plugging Proposal Received by Richard W. Lucey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 10:30 pm Day: 21 Month: April Year: 1984

ACTUAL PLUGGING REPORT 1st plug at 1600' with 50 sx cement, 2nd plug at 750' with 70 sx cement, 3rd plug at 300' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rathole with 15 sx cement.

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Sun (If additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED

DATE 4-25-84

APR 24 1984

INV. NO. 1256

4-21 MAY 09

CONSERVATION DIVISION
1000 Wichita, Kansas

Signed Richard W. Lucey (TECHNICIAN)