

6-18

4-071052

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-051-24,832-00-00

S2 SW SW /4 SEC. 34, 11 S, 19 W
330 feet from S section line
4610 feet from E section line

Operator license# 6194 Lease Jensen well # 1

Operator: E.S.P. Development, Inc. County Ellis

Address: R.R. #1 - Box 18 Well total depth 3697 feet ^{120.15}
Paradise, Kansas 67658 Conductor Pipe: 0 inch @ 0 feet
Bud Eulert Surface pipe 8 5/8 Inch @ 240 feet

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: VonFeldt Drilling Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 18 Month: June Year: 93

Plugging proposal received from: Darrell Krier

Company: VonFeldt Drilling Company Phone: 913-998-4413

Were: 8 5/8" - 240' S.P. cwc. w/160 sx. 60/40 pozmix - 2% gel. - 3% c.c. By Allied Cement. Elv. - 2143' - Anhy. 1453' - Did not penetrate ar buckle - mud condition 42 vis. - 10.1 weight - water loss 8. Proposal 200 sx. 60/40 pozmix - 6% gel. and 1 sx. flocele. Spot and displace all cement through drill pipe. Heavy mud between all plugs.

Plugging Proposal Received by: Marion J. Schmidt
Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 11:30P.M., Day: 18, Month: June, Year: 93

Actual plugging report: VonFeldt Drilling ordered 200 sx. 60/40 pozmix 6% gel. - 1 sx. flocele. Circulated hole. Spotted and displaced all cement through drill pipe - heavy mud between all plugs.

- 1st. plug @ 1500' w/ 25 sx. cement.
- 2nd. plug @ 750' w/100 sx. cement with one sx. flocele.
- 3rd. plug @ 290' w/ 40 sx. cement.
- 4th. plug @ 40' w/ 10 sx. cement.
- 15 sx. in Rathole. - 10 sx. in Mousehole.

Remarks: Cemented by Allied Cement.
Condition of casing(in hole):GOOD X BAD Anhy.plug:YES X NO
Bottom plug(in place):YES X ,CALC ,NO Dakota plug:YES X ,NO
Plugged through TUBING X , CASING . Elevation: 2143 GL

I did[] / did not[X] observe the plugging.

INVOICED

DATE 7-7-93
DIV. NO. 38043

Marion J. Schmidt
DH (agent)

RECEIVED
STATE CORPORATION COMMISSION

JUN 30 1993

Form CP-2/3 CONSERVATION DIVISION
Wichita, Kansas